



| | | | | | | | | |
|---|---|--|---|--|---|---|--|--------------------|
| Client CARMELITES OF MARY IMMACULATE REGISTERED TRUSTEE (CMI HUDUMA PROJECT) P.O.BOX 5459-00506, NAIROBI. | Title PROPOSED DEVELOPMENT ON PLOT LR.NO.NGONG/NGONG/15685. | Title GROUND & UPPER FLOOR PLANS | project status: WORKING DRAWINGS | NOTES:GENERAL 1. All measurements are shown in millimeters. Measurements should not be scaled off the drawing. 2. The contractor must check and verify all dimensions before commencing any work. Any discrepancy must be notified to the architect. 3. All sections should be read as per the floor plan and all discrepancies must be notified immediately to the designer and clarified by consulting the respective consultants' drawings. | CONSTRUCTION 4. Damp proof course must be provided under all external walls at grade. DPC to be minimum 150mm above ground level. 5. All slab at grade to be poured on 100gauge polytheneon 50mm stone dust blinding on compacted hardcore. 6. All soils under slab and around external foundation to be treated for termite control. 7. Window cills must be finished before internal plastering. | scale: 1:100 / 1:50 Date: MARCH. 2017. | designed: drawn: J OBOP. | Consultants |
|---|---|--|---|--|---|---|--|--------------------|